



## CITY OF FOSTER CITY

610 Foster City Boulevard  
Foster City, CA 94404-22222  
Phone: 650 286-3270

### (CIP 301-635) Median Modifications on Foster City Boulevard

#### PRE-BID QUESTIONS AND ANSWERS as of 4/3/25

**Bid Opening Date:** April 9, 2025

	Question	Response	Include in Addendum ?
1	Is there a mandatory pre-bid meeting scheduled for this project?	No mandatory pre-bid meeting scheduled for this project.	
2	Is there a bid bond form included?	A Bond Accompanying Bid is not required for this project.	
3	Which bid item pertains to the prep/furnish/place polyester concrete as pointed out on Plan Page 12 of 15? The plan sheet says it is part of "REMOVE CONCRETE DECK SURFACE". There's no bid item with that description.	Appendix H: Section 02100 Demolition, Removals or Abandonments - Section 3.02B has that work included in the demolition part of the scope. "... shall include concrete refinishing to ensure a smooth and even finish on the structural concrete."	
4	There's also no specification for the PPC overlay. Can you provide one?	For polyester concrete overlay specification, please see Caltrans Standards Section 61 Existing Structures 60-3.04B(2) Materials. <a href="https://dot.ca.gov/programs/construction/construction-manual/section-4-60-existing-structures">https://dot.ca.gov/programs/construction/construction-manual/section-4-60-existing-structures</a>	
5	Is this containment system & joint seal cleaned and re-installed only in the affected median modification area? Or are you looking to clean and re-seal the longitudinal joint for the full length of the bridge?	The reconstruct joint type AL joint seal is to cover the project area only and not the full length of the bridge. The debris containment system should be installed to meet Structural Note 5 and is up to the contractor's discretion.	

6	Please clarify that the bid items for Traffic Control and Erosion Control are to be .15 @ Lump Sum?	Traffic Control and Erosion Control quantities should be 1 Lump Sum. This will be reflected in Addendum #2.	Yes
7	Can you please clarify what the 104 CY's of off-haul pertains to? The demo curb item should be +/- 3 CY's and the 1,424 SF for the pavers at 6" depth is +/- 27 CY's.	Off-Haul line item was intended for earthwork quantities and will be removed from the bid schedule. This will be reflected in Addendum #2.	Yes
8	Are there removals elsewhere? The demo drawing shows legends for multiple items that are not part of this contract or are not shown.	The unidentified asphalt and landscape removals shown on C3.0 are no longer part of the project. The deletion from the legend will be reflected in Addendum #2.	Yes
9	Please clarify if the pavers must be salvaged per the drawings or per the specs they can just be disposed of as there is a big cost differential.	Appendix H: Section 02100 Demolition, Removals or Abandonments - Section 3.05 states the pavers must be salvaged. Excess salvaged pavers are to be transported to City's Corporation Yard.	
10			
11			
12			